

Concrete Takeoff & Cost Estimate

PROJECT	ESTIMATE #	DATE
Meridian Warehouse Slab-on-Grade	SE-SAMPLE-001	07/28/2026
ADDRESS	PREPARED BY	STATUS
4400 Industrial Pkwy, Calgary, AB	Sigma Estimations Team	Sample / Draft

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
Site excavation and sub-base prep	18500	sf	\$0.85	\$15,725.00
Compacted gravel base, 6 in	18500	sf	\$1.10	\$20,350.00
Vapor barrier, 10 mil	18500	sf	\$0.42	\$7,770.00
Rebar, #4 grid reinforcement	42	ton	\$1,150.00	\$48,300.00
Ready-mix concrete, 5 in slab, 4000 psi	285	cy	\$168.00	\$47,880.00
Concrete placement and finishing labor	18500	sf	\$1.95	\$36,075.00
Control joint sawcutting	1850	lf	\$1.35	\$2,497.50
Curing compound application	18500	sf	\$0.28	\$5,180.00
			Subtotal	\$183,777.50
			Contingency (8%)	\$14,702.20
			Estimated Total	\$198,479.70

Scope Notes

Estimate covers slab-on-grade concrete placement including sub-base prep, reinforcement, and finishing for a single-story industrial warehouse floor.

This is a sample document generated for illustrative purposes only. Figures, quantities and pricing shown do not represent an actual project and should not be used for bidding, procurement or construction.