

Drywall Estimate — Hang, Tape & Finish

PROJECT	ESTIMATE #	DATE
Nexus Urban Partners Multifamily Interiors	SE-SAMPLE-001	07/28/2026
ADDRESS	PREPARED BY	STATUS
330 Oakview Terrace, Denver, CO	Sigma Estimations Team	Sample / Draft

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
5/8 in drywall, walls, hung	14200	sf	\$0.62	\$8,804.00
5/8 in drywall, ceilings, hung	6100	sf	\$0.78	\$4,758.00
Taping and mudding, level 4 finish	20300	sf	\$0.95	\$19,285.00
Texture application, orange peel	20300	sf	\$0.45	\$9,135.00
Corner bead and trim installation	1850	lf	\$1.15	\$2,127.50
Sanding and prep for paint	20300	sf	\$0.35	\$7,105.00
Primer coat, walls and ceilings	20300	sf	\$0.28	\$5,684.00
Material delivery and staging	1	ls	\$850.00	\$850.00
Subtotal				\$57,748.50
Contingency (8%)				\$4,619.88
Estimated Total				\$62,368.38

Scope Notes

Estimate covers drywall hang, tape, texture and paint-ready finish for interior partitions across a multifamily residential unit package.

This is a sample document generated for illustrative purposes only. Figures, quantities and pricing shown do not represent an actual project and should not be used for bidding, procurement or construction.