

Masonry Estimate — Brick Veneer

PROJECT	ESTIMATE #	DATE
Cornerstone Retail Plaza Facade	SE-SAMPLE-001	07/28/2026
ADDRESS	PREPARED BY	STATUS
762 Main Street, Brisbane, AU	Sigma Estimations Team	Sample / Draft

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
Brick veneer, standard modular	6200	sf	\$9.85	\$61,070.00
Mortar, type N	620	bag	\$12.50	\$7,750.00
Masonry ties and anchors	6200	ea	\$0.95	\$5,890.00
Through-wall flashing	340	lf	\$6.40	\$2,176.00
Weep vents	210	ea	\$3.25	\$682.50
Scaffolding rental, per week (6 weeks)	6	wk	\$480.00	\$2,880.00
Masonry labor, installation	6200	sf	\$7.20	\$44,640.00
Cleaning and sealing, finished facade	6200	sf	\$0.85	\$5,270.00
			Subtotal	\$130,358.50
			Contingency (8%)	\$10,428.68
			Estimated Total	\$140,787.18

Scope Notes

Estimate covers brick veneer installation on the primary street-facing facade, including mortar, ties, flashing and scaffolding.

This is a sample document generated for illustrative purposes only. Figures, quantities and pricing shown do not represent an actual project and should not be used for bidding, procurement or construction.